

## SOIL EROSION & SEDIMENT CONTROL PLAN

1. Land disturbance will be kept to a minimum; restabilization will be scheduled as soon as practical.
2. Haybale and/or fabric filters will be installed at all culvert outlets and along the tow of all critical cut and fill slopes.
3. Culvert discharge areas will be protected with rip-rap channels; energy dissipators will be provided as necessary.
4. Catchbasins will be protected with haybale filters throughout the construction period and until all disturbed areas are thoroughly stabilized.
5. All erosion and sediment control measures will be constructed in accordance with the standards and specifications of the "Erosion and Sediment Control Handbook", USDA - Soil Conservation Service, Storrs, Connecticut.
6. Erosion and sediment control measures will be installed prior to construction.
7. All control measures will be maintained during the construction period.
8. Additional control measures will be installed during the construction period, if necessary or required.
9. Sediment removed from control structures will be disposed of in a manner which is consistent with the intent of the plan.
10. \_\_\_\_\_

Name

Phone

is assigned the responsibility for implementing this erosion and sediment control plan. This responsibility includes the installation and maintenance of control measures, informing all parties engaged on the construction site of the requirements and objectives of the plan, notifying the Inland Wetland Commission of any transfer of this responsibility and for conveying a copy of the Erosion and Sediment Control Plan if the title to the land is transferred.